

Ref. No: WBGB/PRL/RO/214/2025-26

Date: 24/06/2025

## NOTICE

Inviting tender for Electrical works including Electrical wiring, UPS line, LAN Line for **Lagda Branch** under Purulia Region.

West Bengal Gramin Bank invites sealed tenders from reputed, experienced, and eligible contractors/agencies/suppliers for supply & installation of Electrical Works for **Lagda Branch (VILL: LAGDA, PO: LAGDA PURULIA – 723149)** as per work schedule and specification considering the following terms and conditions. Specification of works are given in **Annexure-A**.

### Scope of Work:

- 1) Electrical wiring and Earthing
- 2) LAN Line
- 3) UPS Line
- 4) Associated Electrical works

### Eligibility Criteria:

- 1) The bidder must have prior experience in undertaking similar renovation works in Banks, Government Offices, or Financial Institutions.
- 2) Valid Trade License and GST Registration Certificate are mandatory.
- 3) Financial soundness and capability to complete the project within the stipulated timeline.

### Important Dates:

- 1) Issue of Tender Document: 24/06/2025
- 2) Last Date for Submission of Tender: **15/07/2025 during office hours**
- 3) Opening of Tender: **16<sup>th</sup> July 2025; 12.30 PM** at Purulia Regional Office, WBGB

### Submission of Tender:

Tenders must be submitted in sealed envelopes, clearly superscribed as "**Tender for Electrical works of Lagda Branch, WBGB**" and addressed to: "The Regional Manager, West Bengal Gramin Bank Purulia Regional Office, Hotel Chhaya-Neer Complex (1<sup>st</sup> Floor), Deshbandhu Road, PURULIA-723101".


### Terms & Conditions:

- 1) The Regional Manager reserves the right to accept or reject any or all tenders without assigning any reason.
- 2) The tenderer must visit the site before submitting the tender to assess the scope of work.
- 3) The supplier shall be responsible for the replacement or repair of any defects discovered within three months of installation at their expenses.
- 4) Uncompromising adherence to material and workmanship quality standards is required.



PURULIA REGIONAL OFFICE  
CHHAYA-NEER COMPLEX (1<sup>st</sup> Floor)  
DESHBANDHU ROAD  
PURULIA - 723101  
EMAIL: ropurulia@WBGBank.co.in

- 5) The quotation must specify the proposed project completion time, and any deviations or delays may result in penalties against the original invoice.
- 6) Payment will be rendered upon satisfactory completion of the work, as outlined in the work order.

  
24/06/25  
**Mr. Santanu Sarkar**  
Regional Manager  
**West Bengal Gramin Bank**  
Purulia Region



## ANNEXURE-A

### SPECIFICATION OF WORK

SI No.	Particulars	Unit	Rate	Amount
1	<b>Copper Earthing</b> Depth 2 meter, and 50 KG salt and 20 kg charcoal. 1'-0 x 1'-0 copper plate & water supply pipe.	2 Unit		
2	<b>Generator and Electric change over</b> Supply of new 63 amp Three phase 4pole changer over switch suitable size iron frame, Complete fittings and fixing etc.	1 Unit		
3	<b>Branch head Main Switch</b> Supply of new 100 amp 440 volts TPN FSU power main switch.	1 Unit		
4	UPS output to switch board line	100 mtr		
5	200 amp TPN bas bar	1 unit		
6	32 amp DP Main switch	1 unit		
7	Main switch, Bus bar, Changeover, DP main switch connection	--		
8	LED Tube light 4" with fittings	18 Nos		
9	Plug point	50 nos		
10	Supply switch board	10 nos		
11	15 AMP note counting machine point at Cash Counter (from house wiring)	2 nos		
12	63AMP Change Over to UPS Input line	20 Mtr		
13	UPS main earthing line (Ground to UPS)	40 Mtr		
14	Ceiling Fan 1200mm (Havells Ambrose/ Crompton Surebreeze/ Atomberg Ameza)	6 Nos		
15	Exhaust Fan (300 MM) iron	1 Nos		
16	Shifting, cleaning and fittings of Electrical items from old building to new building	--		

LAN Line				
SI No.	Particulars	Unit	Rate	Amount
1	Lan plug / IO box point.	8 Nos		
2	LAN line wiring	120 mtr		
3	LAN clipping (D-LINK connector)	10 nos		
4	Shifting of LAN Rack	--		



UPS Fittings				
SI No.	Particulars	Unit	Rate	Amount
1	UPS dismantling	2 Nos		
2	UPS resetting	2 Nos		
3	40 amp DP Isolator (for input light)	2 Set		
4	40amp DP MCB (Havells)	2 Nos		
5	32amp DP changeover	1 Nos		
6	6amp MCB (Havells)	10 Nos		

Tentative time to complete the project: \_\_\_\_\_ Days

Date:

Place:

\_\_\_\_\_  
(Signature with seal)

