



COOCHBEHAR REGIONAL OFFICE
Dinhata Road, Morapora Chowpathi
P.O. & Dist : Coochbehar, 736101
Mail: rocooc@rrubkgb.in

NOTICE FOR SEEKING QUOTATION

Date: 15/07/2025

West Bengal Gramin Bank, Regional Office- Coochbehar invites applications cum sealed quotations from authorized, experienced vendors for the **Electrical** works at our Mathabhanga branch as per annexure and layout attached. Interested vendors are requested to submit the quotation in sealed envelope at Regional Office-Coochbehar as per notice mentioned below.

Name of Work:	Electrical and allied works of MATHABHANGA BRANCH of West Bengal Gramin Bank.
Cost of Tender Document: (Non Refundable)	₹500/- (Rupees Five hundred Only) to be paid by cash or demand draft or Banker's Cheque favoring West Bengal Gramin Bank, Regional Office- Coochbehar, Payable at Coochbehar.
Availability of Tender Documents:	West Bengal Gramin Bank, Regional Office Dinhata Road, Morapora Chowpathi Coochbehar-736101, West Bengal
	OR
	www.wbgb.co.in
Issue of the Tender Documents:	From 15.07.2025 to 04.08.2025 between 10:00 Hrs. to 15:30 Hours, Except Sundays and Holidays.
Time & date of Submission of Tender:	Up to 3:00 P.M. on 04.08.2025
Time and Date of Opening of Tender	12:30 P.M. on 05.08.2025
Venue of the Tender opening:	West Bengal Gramin Bank Regional Office, Dinhata Road, Morapora Chowpathi, Coochbehar-736101, West Bengal
Tender to be addressed to:	To, The Regional Manager West Bengal Gramin Bank Regional Office Dinhata Road, Morapora Chowpathi, Coochbehar-736101 West Bengal



COOCHBEHAR REGIONAL OFFICE
Dinhata Road, Morapora Chowpathi
P.O. & Dist : Coochbehar, 736101
Mail: rocooc@rrubkgb.in

Earnest Money:

2 % of the estimate value

The Tenderer must submit an EMD as mentioned in the form of a demand draft / pay order / Banker's Cheque only in favor of West Bengal Gramin Bank payable at Coochbehar drawn on any nationalized bank (and which shall not bear any interest).

Security Deposit :

5% of the estimate value

Defect Liability Period:

12 (Twelve) months from the date of issue of completion certificate.

Period of Completion:

30 Days from the starting of the work.

Validity of the Tender:

3 (Three) calendar months from the date of submission of Tender

Envelope-I:

Shall contain all the covering letter with the Tender Fees & Earnest Money along with the tender document duly signed

Envelope- II:

Shall contain the Price Bid, dully filled in the Provided Price Bid Tender Document.

MODE OF SUBMISSION

The tender is to be submitted in one envelope having both the separate sealed envelopes I & II being put in the this one envelope and should be sealed properly and addressed to "The Regional Manager, West Bengal Gramin Bank, Regional Office, Dinhata Road, Morapora Chowpathi, Coochbehar-736101, West Bengal". Ph. No. & mail id of the vendor should be mentioned on the main envelope.

ENVELOPE I: (MARKED AS ENVELOPE I)

This envelope shall contain the following:



COOCHBEHAR REGIONAL OFFICE
Dinhata Road, Morapora Chowpathi
P.O. & Dist : Coochbehar, 736101
Mail: rocooc@rrubkgb.in

- k) Forwarding letter without mentioning the cost of Tender value arrived at with quoted rates,
- l) ITR of FY 2023-24, 2022-23, 2021-22.
- m) GST Return (GST 1/3)-2024-25
- n) Work Order / Completion of Work Certificates for Similar kind of work (if available). Tenderer with experience will be given preference.
- o) Work Order of major projects on which the firm is engaged at present if available.
- p) Copy of PAN Card,
- q) Copy of GST Certificate,
- r) Copy of Trade License,
- s) Banker Cheque or DD of tender fees & EMD.
- t) Tender document sign & stamped on each page.

ENVELOPE-2: Price Bid (MARKED AS ENVELOPE II)

This envelope shall contain the following

Envelope Marked II shall contain the Priced Bid submitted on the printed Forms issued by the bank. The tenderer shall quote the final figure both figure and words.

Regional Manager

For and on behalf of
WEST BENGAL GRAMIN BANK

Regional Manager
Regional Office, Cooch Behar
West Bengal Gramin Bank
Coochbehar Region

Satyam Kumar
SATYAM KUMAR
MANAGER, ROCOB
Emp ID: 24550

ELECTRICAL WORK					
SL NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Distribution wiring in 2x22/.3(1.5 sqmm)single core stranded 'FR' PVC insulated & unsheathed copper wire in 20mm size PVC rigid conduit 'FR' with 1x22/0.3(1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire ECC with all accessories embedded in wall/ceiling, to light/fan/call bell points with Modular type switch fixed on GI switch board on wall complete with 2 no. suitable size "Ph& N" copper bar with holes fixed on bakelite/hard rubber insulation over the JB welded chairs incl. Modular (wall matching color) top cover 3 mm thick and incl. suitable size inspection box making earthing attachment painting the GI box and mending good the damages.	35	Pts.		
2	Distribution wiring in 1.1 KV grade 2x22/.3(1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire in 20mm size PVC rigid conduit 'FR' (precision make) with 1.1 KV grade 1x22/0.3(1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire as ECC with all accessories embedded in wall, to 6 A modular socket & Modular type switch fixed on GI switch board incl. modular (wall matching color) top cover 3mm thick and incl. painting the GI box and mending good the damages to original finish.	28	Pts.		
3	Supply fixing & connection light fittings/fans:				
a	2' LED TUBE 8W or Similar approved of Philips/ Havells/ Crompton Greaves. (with all accessories)	7	Each		
b	Supplying and fixing of call bell with modular type push complete with plate and box to be fixed and mending good all damages.	0	Each		
c	12W 150mm Dia round down light or Similar of Philips/ Havells/ Crompton Greaves (Surface mounted LED down light).(Some lights should connected with UPS as necessary at site)	13	Each		
d	36W LED 2'X2' Square light or Similar approved of Philips/ Havells/ Crompton Greaves (High efficiency Surface mounted LED luminaire).(Some lights should connected with UPS as necessary at site)	5	Each		
e	Supply and fixing of 400mm 230V oscillating type Wall mounted Bracket fan to be fixed on wall with allied arrangement. Havells(Plantina)/ Usha/Bajaj make with all accessories.	0	Each		
f	Supply,erection and connection of 6" PVC exhaust fan Louvers Type Including Wall Cutting with Mending damages & Painting etc as required (Havells/Usha/Bajaj) make.	0	Each		
4	TELEPHONE WIRING				
a	Supply and fixing of telephone junction box "Krone/ Henzel" make on wall /furniture/partition with hinged cover and screwed	0	Each		

	type tag strips complete with mending good,painting etc as required				
b	Supply and erection of modular type telephone outlet RJ 11 mounted on suitable plate housed in recessed MS box (Make - TATA TELECOM / SIEMENS / LUCENT)	0	Each		
c	Supplying, Installation, Testing & Commissioning of 10 pair 0.51 sq. mm. telephone unarmored cable in 20 mm PVC pipe. (Make - Finolex / Havells / Polycab)	0	mtr		
5	COMPUTER DATA SYSTEM/LAN WIRING				
a	Supplying and laying of CAT-6 cable through suitable size PVC casing capping from server to HUB,HUB to Computer Data Socket including interconnection mending good etc. as required (Make - Havells / Finolex / Polycab/ KEI)	110	mtr		
b	Supply and fixing on wall/furniture/partition recessed non-modular type Computer data socket (D-Link make) with mounting box & front plate as shown in the drawing complete with mending good etc. as required. (Make - L&T / Anchor-Panasonic/ Crabtree/ Legrand) (For BM-2 points)	5	Each		
6	MAIN LINE WIRING				
a	Supply and laying 4x10 sqmm+1x6sqmm PVC insulated copper wire from Panel board to LDB(Make - Havells / Finolex / Polycab/ KEI)	50	mtr		
b	Supply and laying 2x6sqmm+1x4sqmm PVC insulated copper wire from Panel board to CDB (Make - Havells / Finolex / Polycab/ KEI)	35	mtr		
c	Supply and laying 2x4sqmm+1x2.5sqmm PVC insulated copper wire from TPN MCB DB to power plug(Make - Havells / Finolex / Polycab/ KEI)	80	mtr		
d	Supply and laying 2x2.5sq.mm+1x1.5sqmm pvc insulated copper wire from SPN MCB DB to switch boards (Make - Havells / Finolex / Polycab/ KEI)	25	mtr		
e	Supply and laying 2x16sq.mm+1x10sqmm pvc insulated copper wire (Make - Havells / Finolex / Polycab/ KEI)	15	mtr		
f	Supplying and fixing 250V 6 pin 16A modular plug socket with 16A modular switch and earthing attachment incl. S&F sheet GI box, modular plate and necessary earthing attachment. (Make - L&T/ Anchor-Panasonic/ Crabtree/ Legrand)	5	Each		
7	RAW POINT WIRING				
	Supply and laying 2x6sqmm+1x4sqmm PVC insulated copper wire (MCB DB TO RAW POINT) (Make - Havells/ Finolex/ Polycab/ KEI)	85	mtr		
8	OUT DOOR TYPE GLOW BOARD WIRING				
a	Supply laying of main line with 2x2.5 +1x1.5 sqmm through MS conduit from main panel to glow sign board.(Make - Havells/ Finolex/ Polycab/ KEI)	45	mtr		

b	Supply & fixing of glow sign board programmable timer switch 24 hrs . (Make - L&T / Anchor-Panasonic/ Crabtree/ Legrand)	1	No.s		
9	UPS WIRING				
a	Supply fixing & connection of UPS circuit line with 1.1kv grade PVC insulated non sheathed stranded copper cable of (FRLS) with 2x2.5sqmm+1x1.5sqmm through rigid PVC conduit 20 mmdia 1.6mm wall thickness, with ISI marks, to lay from UPS MCB DB to plug point board . Two nos point to be connected from One circuit. (Make - Havells /Finolex/ Polycab/ KEI)	85	mtr		
b	Supply,fabrication & fixing of computer board made of 2 nos 5 pin 6 A modular socket & 1 No. 5 pin 16 A socket along with 6A & 16A individual switches having fixed with 1 No.LED indicator and 1 No. board fuse on suitable size GI switch board connection & recessed in wall with mending good all damages as per direction of EIC. (Make - L&T / Anchor-Panasonic/ Crabtree/ Legrand)	5	set		
c	Supply,installation,testing & commissioning of Legrand make 32A-3pin wall mounted,industrial type metal clad socket with plug top & 32A SPN MCB control (For UPS Room) (Make - L&T / Anchor-Panasonic/ Crabtree)	4	No.s		
d	Supply laying & connection of UPS incoming power line with 2x10mmsq+1x6mmsq PVC insulated stranded copper wire from PANEL BOARD to UPS incoming power switch . (Make - Havells / Finolex / Polycab/ KEI)	25	mtr		
e	Supplying and fixing 32A change over switch . (Make - L&T / Anchor-Panasonic/ Crabtree/ Legrand)	2	No.s		
10	EARTHING				
a	Earthing with Copper Plate (610x610x3 mm size) having weight of 9.84 kg and 1 No. 25x5mm copper strip (3.20 m long) & 1 No.6 sqmm PVC insulated stranded copper wire (4 m long) incl. S&F 15 mm dia GI pipe(ISI-Medium) protection (4 mt long) to be filled with bitumen, partly under the ground level & partly above ground lvel to an average depth of 3.65 mts below the ground level and restoring the surface duly rammed incl. Providing 3.0 mt long, 25 mm dia GI pipe (ISI-Medium) for periodic treatment, incl. providing masonry enclosure on the top of the earth electrode of overall size 86.36x86.36x46 cm deep (below ground level) complete with cemented brick work (1:6) of 25 cm width, duly plastered with cement mortar (inside) CI hinged inspection cover of size 36.56x35.56 cm with locking arrangement, GI reducer and treatment of soil by using salt & charcoal or coke for plate electrode. (1 no. for main panel and 1 no. for UPS)	2	No.s		
b	Providing and fixing Copper Earth Wire 8 gauge in pvc conduit in Floor / walls From earth pit to earthing station & finally connected to Main Panel Board Complete.	55	mtr		
c	Providing and fixing Pipe Earthing (IS 3043 Code) 3.0m. deep with 40 mm. dia. GI pipe With perforations filled with alternate layers of Charcoal and salt. The item includes Funnel on top in brick	2	set		

	masonry chamber with CI cover for watering purpose complete.				
11	MAIN ELECTRICAL CUBICAL PANEL				
	i) 500 V 100 A TPN HRC fuse-1				
	ii) 500V 63A TPN HRC fuse - 1				
	iii) 500V 63A TPN on Load change over switch - 1				
	iv) 500V 100 A bus bar Cu with BBC on heavy duty porcelain chairs - 2 set				
	v) 500 V 63 A FP MCB-2NO.				
	vi) 230V/415 V 40A(10KA) SP MCB-4No.				
	vii) 230V/415V 25A (10 KA) SP MCB-1 and HAVELLS XPRO (glow sign board)				
	viii) 0-100 Amp. Ammeter with selector switch- 1 Set				
	ix) 0-500V Voltmeter with selector switch - 1 set				
	x) 100/5 CT - 3 Nos				
	xi) LED Indicator lamp - 3 Nos				
	xii) Medium pressure caution Board - 1 No.	1	set		
12	Main Incoming Switch Fuse Unit. Supply fixing of 100 Amps TPN HRC type SFU at WBSEB end for main incoming on MS angle. Frame & 02 nos Cable end box including connection.	1	set		
13	COMPUTER DISTRIBUTION BOARD				
	Supply & installation of following HAVELLS/ LEGRAND make 12 way TPN MCB distribution board with MCB having short circuit breaking capacity of 10KA or RCBO of 100 mA sensitivity having overload short circuit & earth leakage protection complete with neutral, phase & earth bar with 1 No. 40A DP RCBO as incoming 8x6A SPMCB as outgoing to be partially recessed in wall.	1	set		
14	LIGHTING DISTRIBUTION BOARD				
	Supply & installation of following HAVELLS/ LEGRAND make 16 way TPN MCB distribution board with MCB having short circuit breaking capacity of 10KA or RCBO of 100 mA sensitivity having overload short circuit & earth leakage protection complete with neutral, phase & earth bar with 1 No. 40A DP RCBO as incoming 10x6A SPMCB as outgoing to be partially recessed in wall.	1	set		
15	MAIN POWER CABLE				
a	Supplying, laying & fixing 4 core 50 sqmm PVC insulated, XLPEsheathed AL conductor, 1100 v grade armored cable complete with 2 No.s 8 SWG bare GI wire as running earth (main power cable).	25	mtr		
b	Supplying and fixing compression type gland, brass ring and rubber ring for dust & moisture-proof entry of XLPE/PVC armored 4 core 50 sqmm cable.	4	Each		
c	Supplying and fixing finishing 50 sqmm cable ends by soldering with cable sockets and insulated tapes etc. including supplying sockets, soldering materials, tapes etc. and making connection to	4	Each		

	switch, BDB and BBC etc.				
16	AC POWER DB and AC POWER POINT WIRING				
a	Supply & installation of following HAVELLS/ LEGRAND make double door VERTICAL TPN POWER DB with 1 No. 63A TPN MCCB as incoming 8x20A SPMCB as outgoing to be partially recessed in wall.	1	Each		
b	Supply and laying 4x10sqmm+1x6sqmm PVC insulated copper wire from Panel board to AC DB (Make - Havells / Finolex / Polycab/ KEI)	0	mtr		
c	Supply and laying 2x4sqmm+1x2.5sqmm PVC insulated copper wire from AC TPN MCB DB to AC power plugs(Make - Havells / Finolex / Polycab/ KEI)	0	mtr		
d	Supply & fixing 20A 3 pin socket with 20 A starter incl. MS box & matching plug point by chase cutting on wall mending good all damages to original finish,painting as required for AC's. (Make - L&T / Anchor-Panasonic/ Crabtree/ Legrand/ Northwest)	4	Each		
e	Supply,fitting,fixing and connecting Bluestar/ Hitachi/ voltas/ carrier make five star 1.5 ton Split A/C including 1 year warranty.	0	Each		
f	Supply,fitting,fixing and connecting Bluestar/ Hitachi/ voltas/ carrier make five star 1 ton Split A/C including 1 year warranty.	0	Each		
h	Supply and Installation 3CX2.5 sq.mm. Copper Flexible cable for AC indoor to outdoor unit	0	Rmtr.		
i	Supply and Installation 20mm UPVC drain pipe with concil and cementing complete	0	Rmtr.		
17	GENERATOR CABLE				
a	Supplying, laying & fixing 4 core 16 sqmm PVC insulated,XLPE sheathed AL conductor,1100 v grade armoured cable complete with 2 No.s 8 SWG bear GI wire as running earth(main power cable). (Make -Finolex/ Havells/ Mescab/ Polycab/ KEI).	25	mtr		
b	Supplying and fixing compression type gland,brass ring and rubber ring for dust & moisture-proof entry of XLPE/PVC armored 4 core 16 sqmm cable. (Make - Comet/ Braco/ Jainco)	2	Each		
c	Supplying and fixing finishing of XLPE/PVC armored 4core 16 sqmm cable ends by soldering with cable sockets and insulated tapes etc. including supplying sockets,soldering materials,tapes etc. and making connection to switch,BDB and BBC etc. (Make - Comet/ Braco/ Jainco)	2	Each		
18	SUPPLY ITEMS				
a	Supply of CAT-6, 24 Port Patch Panel of GD Sole/D-Link Make	5	Nos.		
b	Supply of 9U. Metal Rack with Glass door.	5	Nos.		
c	Supply of CAT-VI 1 Mtr. Patch Cord	5	Nos.		
d	Supply of CAT-VI 2 Mtr. Patch Cord	5	Nos.		
19	INSTALLATION ITEMS				



COOCHBEHAR REGIONAL OFFICE
Dinhata Road, Morapora Chowpathi
P.O. & Dist : Coochbehar, 736101
Mail: rocooc@rrubkgb.in

a	Installation with crimping of of CAT-6, 24 Port Patch Panel of GD Sole/D-Link Make	5	Nos.		
b	Installation with fixing of 9U. Metal Rack with Glass door.	5	Nos.		
20	LIGHTING CUT OFF :				
	Supply & installing of 32A DP MCB with suitable size metal box complete (for Lighting Cutoff switch near bank entry/exit gate) for 2 nos. LDB CUTT OFF control. (Legrand make)	1	set		
21	UPS MAIN :				
	Supply & installing of 63A 4 pole MCB with suitable size metal enclosure for UPS main control near UPS.	1	set		
22	METER LEED :				
	Supply & Laying of 1100V grade 4 nos. 16 sqmm single core flexible copper wire in rigid PVC conduit/flexible pipe of suitable size from Meter to Kitkat&Kitkat to 125A SFU in meter spot WBSEB requirement.	5	mtr		
	TOTAL				

ওয়েস্ট বেঙ্গল গ্রামীণ ব্যাঙ্ক

(একটি সরকারী সংস্থা)

WEST BENGAL GRAMIN BANK

(A Govt. Enterprise)



PBGB



BGVB



UBKGB

COOCHBEHAR REGIONAL OFFICE
Dinhata Road, Morapora Chowpathi
P.O. & Dist : Coochbehar, 736101
Mail: rocooc@rrubkgb.in

